

Labor

Project: OFR06581 - Demo PVC / Date: 12/02/2009

Delivery Date: 27/02/2009

Nb.	Code	Name	Nb. of Operations	Time	Quantity
Handwork					
1	M 01	Debitare unghi variabil	0 op	5 min	1.00 h
2	M 03	Debitare armatura	0 op	4 min	17.47 h
3	M 04	Fixare armatura	0 op	1 min	2.18 h
4	M 08	Curatare manuala rame, gauri aerisire	0 op	2 min	1.33 h
5	M 09	Curatare manuala cercevele, gauri aerisire	0 op	2 min	2.40 h
6	M 10	Manopera feronerie	0 op	25 min	11.67 h
7	M 11	Debitare baghete geam	0 op	4 min	15.07 h
8	M 12	Manipulare profile /ml profil	0 op	1 min	4.45 h
9	M 13	Manipulare baghete geam /ml profil	0 op	1 min	1.88 h
10	M 27	Manopera 1 min	0 op	1 min	0.17 h
11	M 28	Debitare PVC - 1 capat	0 op	4 min	7.53 h
12	M 29	Debitare PVC - 2 capete	0 op	2 min	4.47 h
13	M 30	Lipire PVC - 1 capat	0 op	2 min	3.70 h
14	M 34	Frezare montant si fixare	0 op	10 min	3.67 h
Total: Handwork					76.98 h
Manopera sticla					
15	M 14	Taiere geam /perimetru	0 op	0 min	0.00 h
16	M 15	Lipire termopan	0 op	0 min	0.00 h
17	M 16	Izolare termopan	0 op	0 min	0.00 h
Total: Manopera sticla					0.00 h
Manopera livrare si montaj					
18	M 17	Pregatire, incarcare /ochi	0 op	10 min	1.67 h
19	M 19	Fixare rama /perimetru	0 op	2 min	0.33 h
20	M 20	Montare geam /geam	0 op	4 min	1.93 h
21	M 21	Reglare feronerie /ccv	0 op	5 min	1.58 h
22	M 24	Demontare tamplarie veche, mediu	0 op	10 min	1.67 h
Total: Manopera livrare si montaj					7.18 h
Total:					84.17 h